



Working Together for a Better Tomorrow, Today.

**UTILITIES DEPARTMENT – PLATTE GENERATING STATION
CITY OF GRAND ISLAND, NEBRASKA**

ELECTROSTATIC PRECIPITATOR REFURBISH – FALL 2020 OUTAGE

ADDENDUM # 1 TO BID DOCUMENTS

ISSUE DATE: August 7, 2020

REVISED BID OPENING DATE

Sealed bids will be received at the office of the City Clerk, 100 E. First Street, PO Box 1968k Grand Island, Nebraska 68802, until [Thursday, August 20, 2020 at 2:15 p.m.](#) FOB the City of Grand Island, freight prepaid for the Electrostatic Precipitator Refurbish – Fall 2020 Outage. All forms within the bid specification should be considered revised to reflect the new bid opening deadline.

ADDITIONAL CLARIFICATIONS: To the Inspection and Maintenance and Bidding sections in Electrostatic Precipitator Refurbish - Fall 2020 Bid Documents

Section 2.2.5B (Page 16) States “Check rapper housings for level.” The contractor shall note any rappers in need of attention as a result of not being level.

There will be some deviation in their vertical position because of the hot roof. However, any that are not effectively rapping should be brought up in the report along with recommendations on how to fix.

Section 2.2.5B (Page 16) States “Remove spring from casing and check for free-standing height, and replace if less than 3.5 in.” shall read “Remove spring from casing and check for free-standing height and replace if spring is broken or showing signs of permanent compression.

We have various rappers in place with different spring heights. We cannot specify the height since they are different.

Section 4.0 Bidding (Page 19) - under the Lump Sum Pricing 6. Repair of Known issues.

Section 2.3.2 Access Doors and Section 2.3.3 High Voltage Bus Duct will remain under the lump sum pricing.

Section 2.3.1 Electrode Rapper system Replacing all 228 of Rapper grounding straps, Replacing all 228 Rapper boot seals. The rapper boot seals will be replaced with split style boot seals. This shall remain under the lump sum.

Replacing rapper guide gaskets will be determined by the inspection report. This should fall under the unit pricing.

Said Addendum #1A is hereby incorporated into the Electrostatic Precipitator Refurbish – Fall 2020 Outage Bid specification Package and shall be considered in the final Contract.

Please acknowledge this Addendum on your BID DATA FORM when submitting your Bid and Acknowledge Receipt of same to knagel@giud.com.